



Test Report : RQB150W12-110S48

150W Quarter Brick 14~160Vdc wide Input Railway DC-DC Converter

■ DESIGN VERIFY TEST

Output Function Test

Input Function Test

Protection Function Test

■ SAFETY TEST

Safety Test

■ RELIABILITY TEST

Environment Test

Other Test

DESIGN VERIFY TEST

OUTPUT FUNCTION TEST

NO	TEST ITEM	SPECICATION	TEST CONDITION	RESULT	VERDITC
1	VOLTAGE ACCURACY	-1% ~ +1 %	I/P:110VDC O/P:FULL LOAD Ta:25°C	-0.53%	P
2	RIPPLE & NOISE	240 mVp-p	I/P:110VDC O/P:FULL LOAD Ta:25°C	209 mV	P
3	LINE REGULATION	-0.2% ~ +0.2%	I/P:14VDC~110VDC O/P:FULL LOAD Ta:25°C	+0.02% ~ +0.01%	P
4	LOAD REGULATION	-0.5% ~ +0.5%	I/P:110VDC O/P: 0% LOAD~FULL LOAD Ta:25°C	-0.02% ~ +0.01%	P
5	HOLD UP TIME	S2(>10ms) C2(>30ms)	I/P:110VDC O/P:FULL LOAD Ta:25°C	16.0ms 37.8ms	P

INPUT FUNCTION TEST

NO	TEST ITEM	SPECICATION	TEST CONDITION	RESULT	VERDITC
1	INPUT VOLTAGE RANGE	14 VDC ~160 VDC	I/P:TESTING O/P:FULL LOAD Ta:25°C	12.31 VDC ~ 160 VDC	P
2.	EFFICIENCY	87.5%	I/P:110VDC O/P:FULL LOAD Ta:25°C	87.96%	P
3	DC CURRENT	1.55 A / FULL LOAD 10 mA / NO LOAD	I/P:110VDC O/P:NO / FULL LOAD Ta:25°C	1.54 A / FULL LOAD 8.2 mA / NO LOAD	P
4	SETUP TIME	< 300mS	I/P:110VDC O/P:FULL LOAD Ta:25°C	185mS	P

PROTECTION FUNCTION TEST

NO	TEST ITEM	SPECICATION	TEST CONDITION	RESULT	VERDITC
1	SHORT PROTECTION	CONTINUOUS	I/P:160VDC O/P:FULL LOAD Ta:25°C	HICCUP MODE AUTOMATIC RECOVERY	P
2	OVER LOAD PROTECTION	120~200%	I/P:110VDC O/P:TESTING Ta:25°C	153.9% HICCUP MODE AUTO-RECOVER	P
3	OVER VOLTAGE	110~150%	I/P:110VDC O/P:TESTING Ta:25°C	132.6% PROTECTION TYPE : SHUTDOWN(LATCH)	P
4	OVER TEMPERATURE	+115°C THEMAL SHUTDOWN	I/P:110VDC O/P:TESTING Ta: TESTING	OK AUTOMATIC RECOVERY	P

CONTROL FUNCTION TEST

	TEST ITEM	SPECICATION	TEST CONDITION	RESULT	VERDICT
1	REMOTE CONTROL	Power on : >3.0~12Vdc or open circuit Power off : R.C <1.2Vdc or short	I/P:110VDC O/P:FULL LOAD Ta:25°C	Power on : R.C>2.0Vdc or Open Power off : R.C<1.8Vdc or Short	P
2	TRIM	-10%~ +10% (Typ) Trim ~ +Vout Trim DOWN Trim ~ -Vout Trim UP Using 2M ohms VR	I/P:110VDC O/P:FULL LOAD Ta:25°C	Trim DOWN -10.4% Trim UP +9.27%	P

SAFETY TEST

SAFETY TEST

NO	TEST ITEM	SPECICATION	TEST CONDITION	RESULT	VERDITC
1	WITHSTAND VOLTAGE	I/P-O/P:3.0K VAC/min I/P-CASE:1.5K VAC/min	I/P-O/P:3.0K VAC/min I/P-CASE:1.5K VAC/min Ta:25°C	I/P-O/P: 0.002mA I/P-O/P: 0.002mA NO DAMAGE	P
2	ISOLATION RESISTANCE	I/P-O/P:500VDC>1000MΩ I/P-CASE: 500VDC>1000MΩ	I/P-O/P:500 VDC I/P-CASE:500 VDC Ta:25°C	I/P-O/P>1000MΩ I/P-CASE>1000 MΩ NO DAMAGE	P

RELIABILITY TEST

ENVIRONMENT TEST

NO	TEST ITEM	SPECICATION	TEST CONDITION	RESULT	VERDICT
1	TEMPERATURE RISE TEST	Please refer to derating curve in specification.			P
2	LOW TEMPERATURE TURN ON TEST	TURN ON AFTER 4 HOURS	I/P:110VDC O/P: FULL LOAD Ta= -40°C	TEST : OK	P

OTHER

NO	TEST ITEM	SPECICATION	TEST CONDITION	RESULT	VERDITC
1	MTBF	MIL-HDBK-217F,GB,25°C TOTAL FAILURE RATE : 5.4054 M.T.B.F : 185K HRS			P

TEST RESULT	TESTER	APPROVAL
PASS	ARCHEN HSIAO	PETER CHENG