



Test Report : SPU03L-12

3W DC-DC Unregulated Single Output Converter

■ DESIGN VERIFY TEST

Output Function Test

Input Function Test

Protection Function Test

■ SAFETY TEST

Safety Test

■ RELIABILITY TEST

Environment Test

DESIGN VERIFY TEST
OUTPUT FUNCTION TEST

NO	TEST ITEM	SPECICATION	TEST CONDITION	RESULT	VERDICT
1	VOLTAGE ACCURACY	-2 % ~ +2 % (Max)	I/P:5VDC O/P:FULL LOAD Ta:25°C	0.80 %	P
2	RIPPLE & NOISE	50 mVp-p (Max)	I/P:5VDC O/P:FULL LOAD Ta:25°C	13 mV	P
3	LINE REGULATION	-12 % ~ +12 % (Max)	I/P:4.5VDC-5.5VDC O/P:FULL LOAD Ta:25°C	-10.9 % ~ +10.9 %	P
4	LOAD REGULATION	-8 % ~ +8 % (Max)	I/P:5VDC O/P:MIN-FULL LOAD Ta:25°C	-3.51 % ~ +2.31 %	P

INPUT FUNCTION TEST

NO	TEST ITEM	SPECICATION	TEST CONDITION	RESULT	VERDICT
1	EFFICIENCY	85 % (Typ)	I/P:5VDC O/P:FULL LOAD Ta:25°C	85.79 %	P
2	DC CURRENT	715 mA / FULL LOAD (Max) 65 mA / NO LOAD (Max)	I/P:5VDC O/P:NO / FULL LOAD Ta:25°C	705 mA / FULL LOAD 59 mA / NO LOAD	P

PROTECTION FUNCTION TEST

NO	TEST ITEM	SPECICATION	TEST CONDITION	RESULT	VERDICT
1	OVER LOAD PROTECTION	Momentary	I/P:5VDC O/P:TESTING Ta:25°C	BROKEN	P
2	SHORT PROTECTION	Momentary	I/P:5.5VDC O/P:FULL LOAD Ta:25°C	BROKEN	P

SAFETY TEST

SAFETY TEST

NO	TEST ITEM	SPECICATION	TEST CONDITION	RESULT	VERDICT
1	WITHSTAND VOLTAGE	I/P-O/P:3000 VDC/min	I/P-O/P:3000 VDC/min Ta:25°C	I/P-O/P: 0.02mA NO DAMAGE	P
2	ISOLATION RESISTANCE	I/P-O/P:500VDC>100MΩ	I/P-O/P:500 VDC Ta:25°C	I/P-O/P>100MΩ NO DAMAGE	P

RELIABILITY TEST

ENVIRONMENT TEST

NO	TEST ITEM	SPECICATION	TEST CONDITION	RESULT	VERDICT										
1	TEMPERATURE RISE TEST	1. ROOM AMBIENT BURN-IN : 13HRS I/P:5VDC O/P:FULL LOAD Ta=25°C 2. HIGH AMBIENT BURN-IN : 8HRS I/P:5VDC O/P:FULL LOAD Ta=85°C			P										
		<table border="1"> <thead> <tr> <th>NO</th> <th>Position</th> <th>P/N</th> <th>1</th> <th>2</th> </tr> </thead> <tbody> <tr> <td>1</td> <td>CASE</td> <td>CENTER</td> <td>55.3°C</td> <td>112.3°C</td> </tr> </tbody> </table>			NO	Position	P/N	1	2	1	CASE	CENTER	55.3°C	112.3°C	
NO	Position	P/N	1	2											
1	CASE	CENTER	55.3°C	112.3°C											
2	LOW TEMPERATURE TURN ON TEST	TURN ON AFTER 13 HOURS	I/P:5VDC O/P: FULL LOAD Ta= -40°C	TEST : OK	P										

TEST RESULT	TESTER	APPROVAL
PASS	PETER	VINCENT ZENG